

BTICINO &gt; Low voltage energy distribution &gt; TIFAST - wiring systems &gt; Vertical distribution terminals



405023

Terminal block of the vertical distribution -  $I_n = 63A$  - 3 file -  $I_{pk} = 20kA$  - supply cables 6-16mmq - drop cables 4 a 10mmq

## Technical features

Standard reference	CEI EN 61439-1/2
Rated current	250A
Series	Tifast

## Documentation

[Instructions Sheet](#)